

Gulf Stream®

Swimming Pool Heat Pumps

PERFORMANCE



EFFICIENCY

10 YEARS PARTS

2 YEARS LABOR



IMPROVED PERFORMANCE
SEE BACK FOR MORE DETAILS



AHRI CERTIFIED™
www.ahridirectory.org

HE-2 SERIES
SEE COMPLETE WARRANTY FOR DETAILS



WWW.GULFSTREAMHEATPUMP.COM



PERFORMANCE AND EFFICIENCY:	INTELLIGENT CONTROL: (Additional wiring may be required)
<p>Ultra-Quiet Design Quiet scroll compressor Commercial grade fan motor designed for quiet operation</p>	<p>Compatible with all external Automation Simple connection and programming Seamless integration with all major brands of automation</p>
<p>4-Sided Evaporator Coil Super-sized for maximum efficiency Higher Performance in all weather Engineered for a smaller footprint</p>	<p>GPS Affordable Spa Automation Isolates the spa, energizes the pump & switches thermostats Plug-ins for 2 actuators Wireless options available</p>
<p>2" Full Flow Titanium Heat Exchanger Pipe size does not reduce once inside the unit Maximum water flow design for higher efficiency Titanium not affected by pool chemistry</p>	<p>Solarwize Solar Heating Controller Solar pool automation for hybrid pool heating control Prioritizes solar pool heating for maximum efficiency Actuator Plug-in & roof sensor connections</p>
<p>Ultimate Warranty Industry Best: 2-Years Labor / 10-Years Parts</p>	<p>Even Heat Maintains the perfect temperature 24-hours a day</p>

ADVANCED ASSEMBLY AND TESTING

<p>Helium Leak Testing 100-times more accurate than the competition Ensures optimized performance in every unit</p>	<p>Mass Flow Charging The most accurate way to ensure proper refrigerant charging Computerized accuracy to 1/100th of an ounce</p>
<p>Rust Proof ABS Cabinet Strong ABS cabinet designed for harsh climates UV inhibitors added for lifetime durability Avoid the metal-cabinet regret</p>	<p>Comprehensive Final Run Test Computerized quality control testing cannot be bypassed Every-component in every-unit tested every-time A "Perfect" unit every time for the ultimate peace of mind</p>

UNIT SPEC	IMPROVED PERFORMANCE		
	HE-110	HE-125	HE-150
BTU/COP AHRI HIGH TEST POINT(80/80/80) LOW TEST POINT (50/63/80)	115,000/6.8 70,000 / 4.0	122,000/6.1 74,000 / 4.0	140,000/6.0 85,000 / 4.0
MIN AMPS / MAX BREAKER	37/40	37/50	37/50
WEIGHT (SHIPPING)	215 LBS (243 LBS)	237 LBS (265 LBS)	239 LBS (267 LBS)
DIMENSIONS (SHIPPING)	31 X 31 X 38 (33 X 31 X 43)	31 X 31 X 42 (33 X 31 X 47)	31 X 31 X 42 (33 X 31 X 47)



WWW.GULFSTREAMHEATPUMP.COM

